GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

OFFICE OF THE SUPERINTENDING ENGINEER, ELECTRICAL DEPARTMENT, BANGALORE.

Abstract Notification.

Attention of the public is hereby invited to the detailed notification dated the 30th September 1938, calling for tenders for constructing a building for combined Central and B.P. & L. Stores at Bangalore, published in Part VI, pages 1773-1775 of the *Mysore Gazette*, dated 13th October 1938. The latest date for receiving tenders is extended upto 2 P.M. on the 31st October 1938.

Abstract Notification dated 7th October 1938.

Attention of the public is hereby invited to the detailed notification dated 5th October 1938, calling for tenders for constructing Electrical Buildings at Kankanhalli and Closepet, published in Part VI, pages 1776-1778 of the *Mysore Gazette*, dated 13th October 1938. The latest date for receiving tenders is 3 P.M. on the 28th October 1938.

Abstract Notification dated 7th October 1938.

Attention of the public is hereby invited to the detailed notification dated 5th October 1938, calling for tenders for constructing one Block of Operators' Quarters with latrine at French-Rocks, published in Part VI, pages 1778-1780 of the *Mysore Gazette*, dated 13th October 1938. The latest date for receiving tenders is 3 P.M. on the 31st October 1938.

Notification dated 14th October 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, upto 3 P.M. on the 12th November 1938, for constructing two blocks of four Linemen's quarters at Dhanavadi, Shimoga Taluk, on the Bhadravathi-Davangere Transmission Line. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of February 1939.

2. The plans, detailed estimate and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 (Three-hundred rupees only) in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing Linemen's Quarters at Dhanavadi, Shimoga Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight (8) days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Charges on account of water, scaffolding materials, implements for setting out, barricading, clearing site, supply of work, etc., that may be found necessary during the execution will not be paid for separately, but should be borne by the Contractor.

Abstract of the estimate for constructing Linemen's quarters at Dhanavadi, Shimoga Taluk.

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		Rs. a. p.
1	Earthwork excavation and filling in basement including watering and ramming	C.yd.	0 3 3	33	
2	Stone jelly in lime mortar concrete for foundation	C.ft.	0 3 3	287	
3	Size stone in clay foundation and basement with bond stones	„	0 3 6	911	
4	Burnt brick in clay superstructure	„	0 3 6	1,692	
5	Burnt brick in lime mortar superstructure ..	„	0 4 3	513	
6	Stone slabs 6″ thick roughly dressed and set in lime	S.ft.	0 9 0	195	
7	Binding wall 6″×6″ of brick in lime mortar and chunam plastered	R.ft.	0 2 6	28	
8	Chunam plastering 2 coats	Sqr.	3 0 0	45·04	
9	Pointing with cement mortar with thread lines ..	„	4 0 0	1·45	
10	White and colour washing, 2 coats	Sqr.	0 4 3	46·49	
11	Roofing with first-class Mangalore tiles on T. W. reepers including wood oiling to reepers ..	„	28 0 0	14·43	
12	Ridge tiles set in mortar and cement pointed ..	R.ft.	0 8 0	77	
13	Ventilating tiles set in mortar and cement pointed	No.	1 8 0	16	
14	T. W. wrought and put up with 2 coats of wood oiling	C.ft.	4 8 0	52·48	
15	T. W. doors with battened shutters, 1″ thick fittings, etc., complete as per drawing ..	S.ft.	1 2 0	156	
16	T. W. windows with battened shutters 1″ thick iron bars, $\frac{5}{8}$″ dia., and fittings, etc., complete as per drawing	„	1 5 0	60	
17	Chocolate painting, 2 coats	Sqr.	3 8 0	4.62	
18	Constructing sinks in bath rooms	No.	5 0 0	4	
19	Providing stone mortar and pestle	„	4 0 0	4	
20	Flooring with 3″ lime concrete and 1″ cement concrete with $\frac{1}{2}$″ thick cement plastering on top	Sqr.	22 0 0	7.58	
21	Constructing parapet wall with brick in lime mortar 2″ high with Cudappah slabs on top with plastering, etc., complete	R.ft.	0 12 0	37	
22	Providing expanded metal trellis work with T. W. frames in front verandah including a door in each as per design	S.ft.	0 10 0	241	
23	Levelling ground	L. S.	..	..	

N.B.—The details given are for one block only.

Notification dated 14th October 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, upto 3 P.M. on the 12th November 1938, for constructing two blocks of four Linemen's quarters at Lingadahalli, Channagiri Taluk, on the Bhadravathi-Davangere Transmission Line. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of February 1939.

2. The plans, detailed estimate and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 (Three-hundred rupees only) in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing Linemen's Quarters at Lingadahalli, Channagiri Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight (8) days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on to the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Charges on account of water, scaffolding materials, implements for setting out, barricading, clearing site, supply of work, etc., that may be found necessary during the execution will not be paid for separately, but should be borne by the Contractor.

Abstract of the estimate for constructing Linemen's quarters at Lingadahalli, Channagiri Taluk.

Item No.	Description of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		Rs. a. p.
1	Earthwork excavation and filling in basement including watering and ramming	C.yd.	0 3 3	33	
2	Stone jelly in lime mortar concrete for foundation	C.ft.	0 3 3	287	
3	Size stone in clay foundation and basement with bond stones	,,	0 3 6	911	
4	Burnt brick in clay superstructure	,,	0 3 6	1,692	
5	Burnt brick in lime mortar superstructure ..	,,	0 4 3	513	
6	Stone slabs 6" thick roughly dressed and set in lime	S.ft.	0 9 0	195	
7	Binding wall 6"×6" of brick in lime mortar and chunam plastered	R.ft.	0 2 6	28	
8	Chunam plastering 2 coats	Sqr	3 0 0	45·04	
9	Pointing with cement mortar with thread lines ..	,,	4 0 0	1·45	
10	White and colour washing, 2 coats	Sqr	0 4 3	46·49	
11	Roofing with first-class Mangalore tiles on T. W reepers including wood oiling to reepers ..	,,	28 0 0	14·43	
12	Ridge tiles set in mortar and cement pointed ..	R.ft.	0 8 0	77	
13	Ventilating tiles set in mortar and cement pointed	No.	1 8 0	16	
14	T. W. wrought and put up with 2 coats of wood oiling	C.ft.	4 8 0	52·48	
15	T. W. doors with battened shutters, 1" thick fittings, etc, complete as per drawing ..	S.ft.	1 2 0	156	
16	T. W. windows with battened shutters 1" thick iron bars, ½" dia., and fittings, etc., complete as per drawing	,,	1 5 0	60	
17	Chocolate painting, 2 coats	Sqr.	3 8 0	4·62	
18	Constructing sinks in bath-rooms	No.	5 0 0	4	
19	Providing stone mortar and pestle	,,	4 0 0	4	
20	Flooring with 3" lime concrete and 1" cement concrete with ½" thick cement plastering on top	Sqr.	22 0 0	7·58	
21	Constructing parapet wall with brick in lime mortar 2' high with Cudappah slabs on top with plastering, etc, complete	R.ft.	0 12 0	37	
22	Providing expanded metal trellis work with T. W. frames in front verandah including a door in each as per design	S.ft.	0 10 0	241	
23	Levelling ground	L. S.	..	..	

N.B.—The details given are for one block only.

Notification dated 14th October 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, upto 3 P.M. on the 12th November 1938, for constructing two blocks of four Linemen's quarters at Thyavange, Channagiri Taluk, on the Bhadravathi-Davangere Transmission Line. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of February 1939.

2. The plans, detailed estimate and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 (Three-hundred rupees only) in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing Linemen's Quarters at Thyavange, Channagiri Taluk." in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be pasted on to the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-estimated and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Charges on account of water, scaffolding materials, implements for setting out, barricading, clearing site, supply of work, etc., that may be found necessary during the execution will not be paid for separately, but should be borne by the Contractor.

Abstract of the estimate for constructing Linemen's quarters at Thyavangi, Channagiri Taluk.

Item No.	Description of work	Unit	Rate	Quantity per block	Rates to be quoted
			Rs. a. p.		Rs. a. p.
1	Earthwork excavation and filling in basement including watering and ramming	C.yd.	0 3 3	33	
2	Stone jelly in lime mortar concrete for foundation	C.ft.	0 3 3	287	
3	Size stone in clay foundation and basement with hand stones	,,	0 3 6	911	
4	Burnt brick in clay superstructure	,,	0 3 6	1,692	
5	Burnt brick in lime mortar superstructure ..	,,	0 4 3	513	
6	Stone slabs 6" thick roughly dressed and set in lime	S.ft.	0 9 0	195	
7	Binding wall 6"×6" of brick in lime mortar and chunam plastered	R.ft.	0 2 6	28	
8	Chunam plastering 2 coats	Sqr.	3 0 0	45·04	
9	Pointing with cement mortar with thread lines ..	,,	4 0 0	1·45	
10	White and colour washing, 2 coats	Sqr.	0 4 3	46.49	
11	Roofing with first-class Mangalore tiles on T. W. reepers including wood oiling to reepers ..	,,	28 0 0	14·43	
12	Ridge tiles set in mortar and cement pointed ..	R.ft.	0 8 0	77	
13	Ventilating tiles set in mortar and cement pointed	No.	1 8 0	16	
14	T. W. wrought and put up with 2 coats of wood oiling	C.ft.	4 8 0	52·48	
15	T. W. doors with battened shutters, 1" thick fittings, etc., complete as per drawing ..	S.ft.	1 2 0	156	
16	T. W. windows with battened shutters 1" thick iron bars, $\frac{5}{8}$" dia., and fittings, etc., complete as per drawing	,,	1 5 0	60	
17	Chocolate painting, 2 coats	Sqr.	3 8 0	4·62	
18	Constructing sinks in bath-rooms	No.	5 0 0	4	
19	Providing stone mortar and pestle	,,	4 0 0	4	
20	Flooring with 3" lime concrete and 1" cement concrete with $\frac{1}{4}$" thick cement plastering on top	Sqr.	22 0 0	7·58	
21	Constructing parapet wall with brick in lime mortar 2" high with Cudappah slabs on top with plastering, etc., complete	R.ft.	0 12 0	37	
22	Providing expanded metal trellis work with T. W. frames in front verandah including a door in each as per design	S.ft.	0 10 0	241	
23	Levelling ground	L. S.	..	..	

N.B.—The details given are for one block only.

L. A. H. WINCKLER,
Superintending Engineer.

6 G